

## Subdivisional Lines, T.1 S., R.30 E., W. M.

Chains		Feet
79.00	Foot of hill & county road, brs. N.W. & S.E.	- 60
80.00	Set stone, 22 x 7 x 6 at foot of hill on N.W. side of canyon, for Cor. to Secs. 23, 24, 25 & 26. Land; hilly & broken, 2nd & 3rd rate.	
	E. on random line bet. Secs. 24 & 25. Var.19°07'E.	
40.00	Set stake for temp. $\frac{1}{4}$ Sec. Cor.	
79.66	Intersect E. Bdy. of Tp., 23 lks. N. of Cor. to Secs. 24 & 25 from which Cor., I run N.89°50' W. on true line bet. Secs. 24 & 25. Var.22°22'E.	25
35.00	Begin to descend.	- 50
39.83	Set stone, 20 x 10 x 5 on W. hillside for $\frac{1}{4}$ Sec. Cor.	- 50
48.50	A ravine, brs. N.W.	+ 30
55.00	A spur, brs. N.W.	+ 20
69.50	A ravine, brs. N.W.	-100
77.50	County road from Butter Creek to Burch Creek, brs. NE. & SW.	- 40
79.66	Cor. to Secs. 23, 24, 25 & 26. Land; eastern part, level. Western part, much broken, 2d & 3rd rate.	
	N. bet. Secs. 23 & 24. Var.19°07'E.	
15.00	On spur, extending S.E.	+120
37.00	A ravine, brs. E.	
40.00	Set stone, 19 x 10 x 6 on S.E. hillside for $\frac{1}{4}$ Sec. Cor.	+ 15
65.50	A ravine, brs. S.E. Var.20°24'E.	+ 30
80.00	Set stone, 18 x 10 x 7 for Cor. to Secs. 13, 14, 23 & 24. Land; hilly & broken, 2nd & 3rd rate.	+200
	E. on random line bet. Secs. 13 & 24. Var.21°22'E.	
40.00	Set stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersected E. Bdy. of Tp., 12 lks. S. of Cor. to Secs. 13 & 24, from which, I run S.89°55' W., on true line bet. Secs. 13 & 24.	