

T. 1 S., R.30 E., W.M.

Chains		Feet
80.00	Set a stone, 25 x 7 x 4 on W. side of spur for Cor. to Secs. 26, 27, 34 & 35 Land; hilly and broken, 2nd and 3rd rate.	+120
	E. on a random line Bet. Secs. 26 & 35. Var. 23° 08' E.	
40.00	Set a stake for Temp. $\frac{1}{4}$ Sec. Cor.	
80.36	Intersected N.&.S. line, 23 lks. S. of Cor. to Secs. 25, 26, 35 & 36, from which Cor., I run S.89° 50' W. on a true line bet. Secs. 26 & 35. Var. 17° 24' E.	
40.18	Set a stone, 18 x 8 x 5 for $\frac{1}{4}$ Sec. Cor. - Var. 20° 53' E.	+20
68.00	A ravine brs. S.W.	-60
80.36	The Cor. to Secs. 26, 27, 34 & 35. Land; eastern part nearly level, western part broken, 2nd rate, small part 3rd rate.	+40
	N. bet. Secs. 26 & 27. Var. 23° 08' E.	
25.00	Highest point	+75
40.00	Set a stone, 18 x 8 x 6 on N.E. hillside for $\frac{1}{4}$ Sec. Cor.	-20
70.00	Foot of hill, a wide canyon, and road brs. N.W. & S.E.	-300
72.00	Across canyon, foot of hill brs. N.W. & S.E.	
80.00	Set a stone, 19 x 7 x 5 on S.W. hillside for Cor. to Secs. 22, 23, 26 & 27. Land; hilly and broken, 2nd & 3rd rate.	+130
	E. on a random line bet. Secs. 23 & 26. Var. 20° 50' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.12	Intersected N.&.S. line at Cor. to Secs. 23, 24, 25, & 26 from which Cor. I run W. on a true line bet. Secs. 23 & 26. Var. 19° 07' E.	