

T.1 S., R.30 E., W.M.

Chains		Feet
2.00	A ravine brs. W.	-30
37.00	On spur extending W.	+400
40.00	Set a stone, 24 x 10 x 8 on N.W. side of spur for $\frac{1}{4}$ Sec. Cor.	-100
	Var. 24° 12' E.	
61.00	A ravine brs. N.W.	-200
77.00	A spur brs. W.	+90
80.00	Set a stone, 22 x 7 x 4 on N.W. side of spur for Cor. to Secs. 21, 22, 27 & 28..	-40
	Land; high broken bluffs, 3rd rate, large part worthless.	
	E. on a random line bet. Secs. 22 & 27	
	Var. 19° 18' E.	
40.00	Set a stake for Temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersected N.&.S. line, 21 lks. S. of Cor. to Secs. 22, 23, 26 & 27, from which Cor., I run S. 89° 51' W. on a true line bet. Secs. 22 & 27.	
	Var. 20° 50' E.	
13.50	Canyon road brs. W.	-100
21.00	Canyon turns to N.W. Road brs. E. & N.W.	
37.00	On spur brs. N.	+140
40.20	Set a stone, 18 x 8 x 6 on N.W. side of spur for $\frac{1}{4}$ Sec. C Cor.	-10
	Var. 21° 56' E.	
45.50	A ravine brs. N.	-70
72.00	Top of hill	+200
80.40	The Cor. to Secs. 21, 22, 27 & 28	-100
	Land; high and very broken, 2nd & 3rd rate.	
	N. bet. Secs. 21 & 22.	
	Var. 19° 18' E.	
1.00	A ravine brs. S.W.	-12
9.00	Top of ridge brs. N.W. & S.E.	+110
31.00	Foot of hill brs. N.W. & S.E.	-350
33.20	Road brs. N.W. & S.E.	