

T. 1 S., R. 30 E., W.M.

Chains		Feet
	N. bet. Secs. 3 & 4.	
	Var. 22° 57' E.	
5.00	A ravine brs. S.W.	-8
40.00	Set a stone, 20 x 7 x 6 for $\frac{1}{4}$ Sec. Cor.	+80
	Var. 20° 18' E.	
78.42	A point on Base-Line, 12 chs. and 23 lks. from one mound and 7 chs. and 13 lks. from another mound, both marked for Cor. to Secs. 32 & 33, T.1 N., R. 30 E., W.M.	
	Set a stone, 18 x 8 x 4 at point of intersection for Cor. to Secs. 3 & 4.	
	Var. 21° 00' E.	
	Land: high and rolling, good 2nd rate.	
	Nov. 1, 1871	
	N. bet. Secs. 32 & 33	
	Var. 21° 40' E.	
40.00	Set a stone, 18 x 6 x 5 for $\frac{1}{4}$ Sec. Cor.	+20
	Var. 19° 08' E.	
53.50	A ravine brs. N.E.	-150
80.00	Set a stone, 25 x 7 x 3 on E. hillside for Cor. to Secs. 28, 29, 32 & 33.	+10
	Land; high hills, 2nd rate.	
	East on a random line bet. Secs. 28 & 33.	
	Var. 21° 16' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.28	Intersected N.&S. line, 45 lks. N. of Cor. to Secs. 27, 28, 33 & 34, from which Cor., I run	
	N. 89° 38' W. on a true line bet. Secs. 28 & 33.	
	Var. 21° 33' E.	
12.50	Creek Road brs. N.&S.	-30
18.10	Butter Creek, 20 lks. wide, runs N.W.	-40
19.75	Foot of hill, brs. N.W. & S.E.	
28.00	On spur, brs. N.	+120
32.50	A ravine, brs. N.E.	-40
40.14	Set a stone, 20 x 8 x 4 for $\frac{1}{4}$ Sec. Cor.	+100