

T.1 S., R.30 E., W.M.

Chains		Feet
	N. bet. Secs. 20 & 21. Var. 18° 10' E.	
15.00	Top of hill	+120
25.50	A ravine brs. E.	-120
40.00	Set a stone, 20 x 7 x 5 on S.E. hillside for $\frac{1}{4}$ Sec. Cor. Var. 21° 20' E.	+150
45.00	Top of hill	+ 40
80.00	Set a stone, 20 x 8 x 6 on N. side of hill for Cor. to Secs. 16, 17, 20 & 21	-300
<u>Land; high & broken, 2nd & 3rd rate, part worthless.</u>		
	East on a random line bet. Secs. 16 & 21 Var. 21° 32' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.52	Intersected N. & S. line, 32 lks. N. of Cor. to Secs. 15, 16, 21 & 22, from which Cor., I run N. 89° 46' W. on a true line bet. Secs. 16 & 21. Var. 21° 55' E.	
40.26	Set a stone, 18 x 10 x 6 on W. hillside for $\frac{1}{4}$ Sec. Cor. Var. 22° 00' E.	-180
62.20	Butter Creek, 30 lks. wide, runs N.	
67.50	Foot of hill, brs. N. & S.	
80.52	The Cor. to Secs. 16, 17, 20 & 21 Land; hilly and broken. Small part on Creek, 1st rate, remainder, 2nd & 3rd rate. Timber; only a few cotton-wood trees, and willow and alder brush. Nov. 2, 1871	+180
	N. bet. Secs. 16 & 17. Var. 21° 32' E.	
9.00	A ravine brs. N.E.	-140
34.00	Butter Creek, 30 lks. wide, runs N.W.	- 50
40.00	Set a stone, 25 x 12 x 6 at foot of hill for $\frac{1}{4}$ Sec. Cor. Var. 20° 08' E.	+ 10
44.25	On rocky point, brs. N.W.	+ 80
54.50	A canyon, brs. S.W.	* 50