

T. 1 S., R. 30 E., W.M.

Chains		Feet
80.00	Set a stone, 20 x 8 x 6 on S.E. hillside for Cor. to Secs. 29, 30, 31 & 32. Land; high hills, 2nd & 3rd rate, small part worthless.	+200
	East on a random line bet. Secs. 29 & 32. Var. 19° 08' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
79.84	Intersected N. & S. line, 44 lks. S. of Cor., to Secs. 28, 29, 32 & 33, from which Cor. I run S. 89° 41' W. on a true line bet. Secs. 29 & 32. Var. 21° 16' E.	
15.00	Top of ridge, brs. N.E. & S.W.	+200
39.92	Set a stone, 16 x 8 x 5, on W. side of ridge for $\frac{1}{4}$ Sec. Cor. Var. 21° 00' E.	
44.50	Foot of hill, brs. N.E. & S.W.	- 60
47.25	Road brs. N.E. & S.W.	
48.00	A spring branch runs N.E.	
52.50	Foot of hill, on N.W. side of canyon, brs. N.E. & S.W.	
79.84	The Cor. to Secs. 29, 30, 31 & 32. Land; hilly and broken, 2nd & 3rd rate.	+220
	West on a random line bet. Secs. 30 & 31. Var. 19° 08' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Secs. Cor.	
78.68	Intersected W. Bdy. of Tp., 37 lks. S. of Cor. to Secs. 30 and 31, from which Cor., I run S. 89° 44' E. on a true line bet. Secs. 30 & 31. Var. 21° 57' E.	
38.68	Set a stone, 19 x 7 x 5 for $\frac{1}{4}$ Sec. Cor. Var. 22° 34' E.	- 20
65.00	Begin to descend.	
78.68	The Cor. to Secs. 29, 30, 31 & 32. Land: W. 65 chs., high table land; remainder, broken 2nd and 3rd rate.	-180