

T. 1 S., R. 30 E., W.M.

Chains		Feet
	S. 89° 37' E. on a true line bet. Secs. 19 & 30. Var. 21° 00' E.	
38.45	Set a stone, 22 x 6 x 5 for $\frac{1}{4}$ Sec. Cor. Var. 21° 38' E.	
50.00	Begin to descend	
68.50	A ravine brs. S.E.	-160
78.45	The Cor. to Secs. 19, 20, 29 & 30 Land; western part nearly level, eastern part much broken 2nd & 3rd rate, part worthless. Nov. 4, 1871	+ 80
	N. bet. Secs. 19 & 20. Var. 19° 43' E.	
5.00	A ledge of basalt rock, 6 ft. high, brs. E.&W.	+ 50
10.00	On small table land	+ 30
40.00	Set a stone, 20 x 7 x 5 for $\frac{1}{4}$ Secs. Cor. Var. 22° 47' E.	
61.00	Begin to descend	
74.50	A ravine brs. N.W.	-220
80.00	Set a stone, 16 x 10 x 6 on S.W. hillside for Cor. to Secs. 17, 18, 19 & 20. Land; high and part broken, 2nd & 3rd rate.	+ 50
	East on a random line bet. Secs. 17 & 20. Var. 21° 56' E.	
40.00	Set a stake for temp. $\frac{1}{4}$ Sec. Cor.	
79.76	Intersected N. & S. line, 30 lks. N. of Cor. to Secs. 16, 17, 20 & 21, from which Cor., I run N. 89° 47' W. on a true line bet. Secs. 17 & 20. Var. 21° 32' E.	
7.75	A canyon brs. N.E.	-60
39.88	Set a stone, 18 x 10 x 4 on S.E. hillside for $\frac{1}{4}$ Secs. Cor. Var. 19° 34' E.	+ 340
62.00	Top of hill	+ 60
79.76	The Cor. to Secs. 17, 18, 19 & 20.	