

South Bdy. of T. 1 S., R.31 E., W.M.

Chains		Feet
	<p>pits, trench, etc., as per instructions.</p> <p>Land; level.</p> <p>Soil; good 2nd rate.</p>	
	<p>E. on N. Bdy. of Sec. 5</p> <p style="text-align: right;">Var. $19\frac{1}{2}^{\circ}$ E.</p> <p>Descend hill .</p>	
12.50	Brook, 2 lks. wide, runs N.E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, with charred stake, pits, trench, etc. as per instructions.	
54.60	Ravine brs. N.	
80.00	Set stone, 28 x 10 x 6 ins. for Cor. to Secs. 4, 5, 32 & 33.	-300
	<p>Land; rolling.</p> <p>Soil; 2nd rate.</p>	
	<p>E. on N. Bdy. of Sec. 4.</p> <p style="text-align: right;">Var. $18^{\circ} 45'$ E.</p> <p>Descend hill.</p>	
40.00	Set stone, 20 x 15 x 10 ins. for $\frac{1}{4}$ Sec. Cor.	-300
45.00	Foot of hill.	
50.75	E. Fork of Birch Creek, 10 lks. wide, runs N.W.	
53.00	Road brs. N.W. & S.E.	
60.00	Ascend hill.	
80.00	Set stone, 24 x 12 x 8 ins. for Cor. to Secs. 3, 4, 33 & 34.	+400 ⁰⁰
	<p>Land; hilly.</p> <p>Soil; 2nd rate.</p> <p>Some cotton-wood timber on the Creek.</p>	
	<p>E. on N. Bdy. to Sec. 3.</p> <p style="text-align: right;">Var. 22° E.</p> <p>Ascend hill.</p>	
40.00	Set stone, 17 x 9 x 7 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 2, 3, 34, & 35, in mound of	