

T.1 S., R. 31 E., W.M.

Chains		Feet
80.70	Intersect N. Bdy. 30 lks. W. of Cor. to Secs. 2 & 3, from which Cor.	
	I run	
	S. 0° 13' W. on a true line bet. Secs. 2 & 3.	
40.70	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.70	The Cor. to Secs. 2, 3, 10 & 11.	
	Land; rolling.	
	Soil; 2nd rate.	
	Nov. 13, 1864	
	N. bet. Secs. 33 & 34.	
40.00	Set stone, 16 x 8 x 5 for $\frac{1}{4}$ Sec. Cor.	
75.50	Var. 20° E.	
80.00	Set stone, 20 x 16 x 16 for Cor. to Secs. 27, 28, 33 & 34.	
	Land; rolling.	
	Soil; 1st rate.	
	E. on a random line bet. Secs. 27 & 34.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.70	Intersect N. & S. line N. of Cor. to Secs. 26, 27, 34 & 35 from which Cor.,	
	I run	
	N. 89° 50' W. on a true line bet. Secs. 27 & 34.	
24.00	Deep ravine, brs. N.E.	
39.85	Set stone, 17 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.	
79.70	The Cor. to Secs. 27, 28, 33 & 34.	
	Land; rolling.	
	Soil; 2nd rate.	
	N. bet. Secs. 27 & 28.	
	Var. 24° E.	
	Descend W. slope of hill.	
40.00	Set stone, 20 x 15 x 5 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 21, 22, 27 & 28, in mound of earth, with charred stake, pits, etc., as per instructions.	