

3.

E. Bdy. of T. 1 S., R. 32 E., W.M.
 As surveyed by the same Deputy Surveyor.
 Under the same Contract and date.

Chains		Feet
	I begin at the Cor. to Tps. 1 & 2 S., Rs. 32 & 33 E., thence N. on E. Bdy. of Secs. 36. <div style="text-align: right;">Var. 19° E.</div>	
35.00	Ravine brs. N.W.	
40.00	Set stone, 24 x 12 x 12 ins. for $\frac{1}{4}$ Sec. Cor.	
50.00	Descend hill.	
52.70	Daily's Road brs. E. & W.	
80.00	Set post for Cor. to Secs. 30, 31, 25 & 36, in mound of earth, with charred stake, pits, trench, etc., as per instructions. Land; hilly. Soil; 2nd rate.	-400
N. on E. Bdy. of Sec. 25. <div style="text-align: right;">Var. 21° 30' E.</div>		
2.50	Foot of hill, ascend.	
25.00	Top of hill, N.W. & S.E., descend.	
40.00	Set stone, 18 x 10 x 4 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 24, 25, 19 & 30, in mound of earth, with charred stake, pits, trench, etc., as per instructions. Land; hilly. Soil; good 2nd rate.	-500
N. on E. Bdy. of Sec. 24. <div style="text-align: right;">Var. 22° 30' E.</div>		
	Descend hill.	
23.50	House brs. N. 5° E., 15.00 chs. dist.	
30.75	Foot of hill, Stewart Creek, dry, brs. N.W.	-400
33.50	Ascend hill.	
40.00	Set stone, 22 x 6 x 6 ins. for $\frac{1}{4}$ Sec. Cor.	
54.00	Top of hill, brs. E. & W.- descend.	
80.00	Set post for Cor. to Secs. 13, 18, 19 & 24, in mound of earth, with charred stake, pits, trench, etc., as per instructions. Land; hilly. Soil; good 2nd rate.	