

Subdivisional lines, T, 1 S., R. 32 E., W.M.

Chains		Feet
	Land; hilly Soil; 2nd rate.	
	N. bet. Secs. 22 & 23 Descend Var. 20° E.	
27.50	Daily's Road brs. N.W. & S.E.	
40.00	Set stone, 18 x 10 x 8 for $\frac{1}{4}$ Sec. Cor. Foot of hill.	
80.00	Set post for Cor. to Secs. 14, 15, 22 & 23, in mound of earth, with charred stake, pits, etc., as per instruc- tions. Land; gently rolling. Soil; 2nd rate.	
	E. on a random line bet. Secs. 14 & 23.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.80	Intersect N. & S. line, 15 lks. S. of Cor. to Secs. 13, 14, 23 & 24, from which Cor. I run S. 89° 54' W. on a true line bet. Secs. 14 & 23. Descend hill.	
25.80	Stewart Creek, dry bed, runs N.W.	
32.72	Road brs. N.W. & S.E.	
39.90	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
79.80	The Cor. to Secs. 14, 15, 22 & 23. Land; gently rolling. Soil; good 2nd rate.	-250
	N. bet. Secs. 14 & 15. Var. 19 $\frac{1}{2}$ ° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc. as per instructions.	
71.50	Road brs. N.W. & S.E.	
80.00	Set post for Cor. to Secs. 10, 11, 14 & 15, in mound of earth, with charred stake, pits, etc., as per instructions.	