

Subdivisional lines, T. 1 S., R. 32 E., W.M.

Chains		Feet
	<p>Land; level. Soil; 1st rate.</p>	
	<p>N. on a random line bet. Secs. 2 & 3. Var. 20° E.</p>	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.74	Intersect N. Bdy. at Cor. to Secs. 2 & 3, from which Cor. I run	
	S. on a true line bet. Secs. 2 & 3.	
40.74	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc. as per instructions.	
80.74	The Cor. to Secs. 2, 3, 10 & 11. Land; level. Soil; 1st rate.	
	<p>N. bet. Secs. 33 & 34. Ascend hill</p>	
40.00	Set stone, 15 x 15 x 10 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 18 x 8 x 6 for Cor. to Secs. 27, 28, 33 & 34 Land; hilly. Soil; 2nd rate.	+500
	<p>E. on a random line bet. Secs. 27 & 34.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersect N. & S. line at Cor. to Secs. 26, 27, 34 & 35, from which Cor. I run	
	W. on a true line bet. Secs. 27, & 34. Descend hill.	
40.20	Set stone, 24 x 8 x 4 for $\frac{1}{4}$ Sec. Cor.	
50.00	Ravine brs. N.E.	
80.40	The Cor. to Secs. 27, 28, 33 & 34. Land; rolling. Soil; 2nd rate.	

Oct. 16, 1864