

Subdivisional line, T. 1 S., R. 32 E., W.M.

Chains		Feet
	N. bet. Secs. 32 & 33. Descend hill.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 28, 29, 32 & 33, in mound of earth, with charred stake, pits, trench, etc., as per instructions. Land; gently rolling. Soil; 2nd rate.	
	E. on a random line bet. Secs. 28 & 33.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.60	Intersect N. & S. line, at Cor. to Secs. 27, 28, 33 & 34, from which Cor. I run W. on a true line bet. Secs. 28 & 33.	
40.60	Set stone, 24 x 18 x 6 for $\frac{1}{4}$ Sec. Cor.	
46.00	Bluff, 22 ft. high, brs. N. & S.	
47.50	Foot of bluff.	
54.50	E. fork of Birch Creek, 10 lks. wide, runs. N.	
69.00	Road brs. N. & S.	
80.60	The Cor. to Secs. 28, 29, 32 & 33. Land; rolling. Soil; 1st rate.	
	N. bet. Secs. 28 & 29. Var. $18\frac{1}{2}^{\circ}$ E.	
40.00	Set stone, 18 x 8 x 8 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 20, 21, 28 & 29, in mound of earth, with charred stake, pits, etc., as per instructions. Land; gently rolling. Soil; 1st rate.	
	E. on random line bet. Secs. 21 & 28.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	