

Subdivisional lines, T. 1 S., R. 32 E., W.M.

Chains		Feet
	N. bet. Secs. 17 & 16. Var. 19° E.	
18.00	House brs. S.55° E., 16 chs. dist.	
20.27	" " N.80° E., 7 " "	
30.50	Touch Creek, course N.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
45.00	Dry bed of Birch creek, course N.W.	
70.70	Road brs. N.5° E., S. 5° W.	
79.00	Main Birch Creek, 10 lks. wide, runs N.E.	
80.00	Set post for Cor. to Secs. 8, 9, 16 & 17, in mound of earth, with charred stake, pits, etc., as per instructions.	
	Land; gently rolling. Soil; 1st rate.	
✓	E. on a random line, bet. Secs. 9 & 16.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.50	Intersect N. & S. line, 50 lks. N. of Cor. to Secs. 9, 10, 15 & 16, from which, $\frac{1}{4}$ run, N.89° 39' W. on a true line bet. Secs. 9 & 16.	
40.25	Set stone, 18 x 12 x 10 for $\frac{1}{4}$ Sec. Cor.	
66.00	Enter field, brs. N.E. & S.W.	
79.00	Birch Creek, 10 lks. wide, runs N.E.	
80.50	The Cor. to Secs. 8, 9, 16 & 17. Land; rolling. Soil; 1st rate.	
✓	N. bet. Secs. 8 & 9. Var. 20° E.	
3.00	Touch Creek	
7.00	Spring brook, 3 lks. wide, runs E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 4, 5, 8 & 9, in mound of earth with charred stake, pits, etc., as per instructions. Land; level. Soil; 1st rate.	