

Subdivisional lines, T. 1 S., R.32 E., W.M.

Chains		Feet
	W. on a true line bet. Secs. 29 & 32.	
18.15	Ravine brs. N.E. Ascend hill.	
39.90	Set stone, 18 x 12 x 5 for $\frac{1}{4}$ Sec. Cor.	
79.80	The Cor. to Secs. 29, 30, 31 & 32	200
	Land; rolling.	
	Soil; good 2nd rate.	
	W. on a random line bet. Secs. 30 & 31.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect W. Bdy. at Cor. to Secs. 30 & 31, from which Cor. I run	
	E. on a true line bet. Secs. 30 & 31.	
40.00	Set stone, 16 x 12 x 6 for $\frac{1}{4}$ Sec. Cor.	
80.00	The Cor. to Secs. 29, 30, 31 & 32.	
	Land; level.	
	Soil; 1st rate.	
	N. bet. Secs. 29 & 30.	
	Var. $20\frac{1}{2}^{\circ}$ E.	
	Descend hill.	
40.00	Set stone, 15 x 15 x 6 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 18 x 10 x 10 for Cor. to Secs. 19, 20, 29 & 30.	150
	Land; rolling.	
	Soil; 1st rate.	
	E. on a random line bet. Secs. 20 & 29.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.25	Intersect N. & S. line at Cor. to Secs. 20, 21, 28 & 29, from which, I run	
	W. on a true line bet. Secs. 20 & 29.	
	Ascend hill.	
39.63	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions. Top of hill.	
79.25	The Cor. to Secs. 19, 20, 29 & 30.	
	Land; gently rolling.	
	Soil; 1st rate.	

Oct. 18, 1864.