

Subdivisional lines, T. 1 S., R. 32 E., W.M.

Chains		Feet
	W. on a random line bet. Secs. 7 & 18.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.70	Intersect W. Bdy.; 12 lks. N. of Cor. to Secs. 7 & 18, from which I run, N. 89° 55' E. on a true line bet. Secs. 7 & 18.	
39.70	Set stone, 18 x 15 x 15 for $\frac{1}{4}$ Sec. Cor.	
79.70	The Cor. to Secs. 7, 8, 17 & 18. Land; level. Soil; 1st rate.	
	N. bet. Secs. 7 & 8. Var. 20° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set stone, 18 x 10 x 10 for Cor. to Secs. 5, 6, 7 & 8. Land; rolling. Soil; 1st rate.	
	E. on a random line bet. Secs. 5 & 8.	
40.00	Set post for Temp. $\frac{1}{4}$ Sec. Cor.	
79.40	Intersect N. & S. line at Cor. to Secs. 4, 5, 8, & 9, from which Cor., I run W. on a true line bet. Secs. 5 & 8.	
39.70	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
79.40	The Cor. to Secs. 5, 6, 7 & 8. Land; level. Soil; 1st rate.	
	W. on a random line bet. Secs. 6 & 7.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect W. Bdy. of $\frac{1}{4}$ Sec. at Cor. to Secs. 6 & 7, from which I run E. on a true line bet. Secs. 6 & 7.	
40.00	Set stone, 18 x 14 x 10 for $\frac{1}{4}$ Sec. Cor.	
80.00	The Cor. to Secs. 5, 6, 7 & 8. Land; gently rolling. Soil; 1st rate.	