

Subdivisional lines T. 1 S., R. 32 E., W.M.

Chains		Feet
	N. on a random line bet. Secs. 5 & 6. Var. 19° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.50	Intersect N. Bdy., 60 lks. E. of Cor. to Secs. 5 & 6, from which, I run S. 26' E. on a true line bet. Secs. 5 & 6.	
40.50	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.50	The Cor. to Secs. 5, 6, 7 & 8. Land; gently rolling. Soil; 1st rate. Oct. 19, 1864.	
General Description.		
<p>The quality of land in this Tp. is above the common average of the land in this part of Oregon.</p> <p>The north & west portions of the Tp. is level or gently rolling. Soil, 1st rate.</p> <p>The South-eastern portion is hilly and is very fine grass land. Soil, 2nd rate.</p> <p>There are a large number of settlers in this Township.</p> <p>There is an abundance of water and timber, being numerous creeks with heavily wooded banks, consisting of cottonwood and birch.</p>		
<p>East Bdy. of T. 1 S., R. 32 E., W.M. As surveyed by Zenas F. Moody, U.S. Deputy Surveyor. Under Contract No. 164 Dated Oct. 4, 1871</p>		
	S. on the E. Bdy. of Sec. 1. Var. 19° 45' E.	
40.00	Set stone, 17 x 12 x 10 for $\frac{1}{4}$ Sec. Cor.	
65.14	Hawthorne Creek flows W.	
80.00	Set stone, 20 x 12 x 9 for Cor. to Secs. 1, 12, 6 & 7. Land; rolling: Soil; good. Good grass.	