

T. 1 S., R. 32 E., W.M.

Chains		Feet
	N. on a random bet. Secs. 1 & 2. Var. 20° E.	
40.00	II found old $\frac{1}{4}$ Sec. Cor., charred stake, pits and mound.	
79.90	Intersect Base Line 17.37 chs. W. of Cor. to Secs. 35 & 36 of T.1 N., R.32 E. I could find no trace of old Closing Cor. and set a basalt stone, 12 x 9x 7 ins., 8 ins. in ground for Closing Cor. to Secs. 1 & 2, marked 1 notch on E., 5 on W. edges, C.C. on S. face. Thence I run S. on true line.	
11.10	Wagon Road, course E. & W.	
39.90	Set a basalt stone, 12 x 8 x 6 ins., 8 ins. in the old mound for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 in. Raised mound of stone, 5 $\frac{1}{2}$ ft. dist., 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.	
79.90	To Cor. to Secs. 1, 2, 11 & 12. Land; rolling. Soil; 2nd rate. No timber, poor grass.	
July 15, 1887.		
General Description.		
This Township is rolling; soil, 1st & 2nd rate. Poor grass Cottonwood and underbrush along Mc Kay Creek.		