

South Bdy. of T. 1 S., R. 33 E.,
As surveyed by James P. Currin & James E. Noland,
U.S. Deputy Surveyors, under their special Contract
Dated May 4, 1887.

Chains		Feet
	From Cor. to Tps. 1 & 2 S., Rs. 33 & 34 E., I run W. on a true line bet. Tps. 1 & 2 S., R. 33 E. Var. 22 ° E.	
2.25	Canyon, course N.	- 50
15.50	Trail on Summit of Ridge	+300
24.10	Gulch, course N.	-200
31.75	Summit, course N.	+200
40.00	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground for 1/4 Sec. Cor., marked 1/4 on N. face. Raised mound of stone alongside. Pits impossible.	
70.55	Canyon, course N.W.	-600
80.00	To a pine tree, 24 ins. diam., which I marked for Cor. to Secs. 1, 2, 35 & 36, T.1 S., S.35 on N.W.; R.33 E., S.36 on N.E.; T.2 S., S.1 on S.E. and S.2 on S.W. 1 notch on E. and 5 notches on W. edges. No bearing trees in limits Raised mound of stone alongside. Land; mountainous, 80.00 chs. No timber. Good bunch grass. Soil; 3rd rate.	
	W. on a true line bet. Secs. 2 & 35. Var. 21° E.	
14.40	Canyon, water in holes- E. North	-300
24.00	Summit, course N.	+300
39.75	Canyon, course N.E.	-200
40.00	Set basalt stone, 10 x 9 x 7 ins., 7 ins. in ground for 1/4 Sec. Cor., marked 1/4 on N. face. Raised mound of stone alongside. Pits impracticable.	
47.50	Summit	+200
57.25	Canyon, water in holes, course N.E.	-200
80.00	Set a basalt stone, 26 x 10 x 8 ins., 19 ins. in ground for Cor. to Secs. 2, 3, 34 & 35. Marked 2 notches on E. and 4 on W. edges. Raised mound of stone alongside. Pits impracticable. Land; rough and mountainous, 80.00 chs. Scattering pine timber in canyons. Bunch grass. Soil, 3rd rate	+300