

T. 1 S., R. 33 E., W.M.

Chains		Feet
28.00	Leave Creek.	
40.00	An alder, 5 ins. diam., which I mark $\frac{1}{4}$ S. on W. face for $\frac{1}{4}$ Sec. Cor., from which, An alder, 4 ins. diam., brs. N.88° E., 17 lks. dist., marked $\frac{1}{4}$ S., B.T. An alder, 4 ins. diam., brs. S. 70° W., 4 lks. dist., marked $\frac{1}{4}$ S., B.T.	
50.00	McKay Creek, course N.20° W., 20 lks. wide	
63.00	Leave Creek bottom.	
80.00	Set a post, 48 x 4 x 4 ins., 2 ft. in the ground for Cor. to Secs. 1, 6, 7 & 12, marked T. 1 S., S.1 on N.W., S.6 on N.E., R.34 E., S.7 on S.E., R. 33 E., S.12 on S.W. faces, with 5 notches on S. and 1 on N. edges, from which, A pine, 12 ins. diam., brs. N.25° E., 93 lks. dist., marked T.1 S., R.34 E., S.6, B.T. A pine, 14 ins. diam., brs. N.25° W., 135 lks. dist., marked T.1 S., R.33 E., S.1, B.T. No other tree in limits. Raised mound of stone alongside. Pits impracticable. Land; mountainous, 38.50 chs. Gravelly bottom, 41.50 chs. Soil; 4th rate. Timber; pine and cottonwood.	
	N. bet. Sec. 1 & 6. Var. 19° E.	
6.00	Canyon, course W.	50
18.75	" " "	100
34.00	Top of Ridge.	250
40.00	Set a basalt stone, 10 x 10 x 8 ins., 7 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, A pine, 12 ins. diam., brs. N.28° E., 17 lks. dist., marked $\frac{1}{4}$ S., B.T. No other tree in limits. Raised a mound of stone alongside. Pits impracticable.	