

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	N. 89° 47' W. on a true line. Descend side hill sloping N.	
15.00	Branch, 15 lks. wide, water in holes at the bottom of canyon.	-400
30.00	Top of Ridge, course S.	+200
40.00	Set a basalt stone, 12 x 10 x 5 ins., 8 ins. in ground, marked $\frac{1}{4}$ on N. face for $\frac{1}{4}$ Sec. Cor. Raised a mound of stone around it. Pits impracticable.	
41.75	Gulch, course S. Ascend mountain.	- 50
80.00	To Cor. to Secs. 23, 24, 25 & 26. Land; rough and mountainous., 80 chs. Pine timber in canyons, good bunch grass. Soil; 4th rate.	+700
	N. bet. Secs. 23 & 24. Var. 16° 30' E.	
3.00	Top of mountain Descend.	+100
38.00	Gulch, course E.	-100
40.00	Set basalt stone, 16 x 16 x 16 ins., 11 ins. in ground, marked $\frac{1}{4}$ on W. face for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around it. Pits impracticable.	
72.00	Top of mountain, course S.W. Descend.	+150
75.00	Brush thicket.	
80.00	Set basalt stone, 18 x 8 x 7 ins., 14 ins. in ground, marked with 3 notches on S. edge and 1 notch on E. edge for Cor. to Secs. 13, 14, 23 & 24. Raised a mound of stone around it. Pits impracticable. Land; rough and mountainous. Bunch grass, 80 chs. Soil; 4th rate.	+600
	July 11, 1887.	
	E. on random line bet. Secs. 13 & 24. Var. 21° E.	