

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect Tp. line, 7 lks. S. of Cor. to Secs. 12, 13, 7 & 18. Thence I run, S. $89^{\circ} 57'$ W. on a true line. Ascend.	
20.00	Bluff of rock, 12 ft. high	+500
40.00	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised a mound of stone around it. Pits impracticable.	
64.00	Top of hill.	+100
80.00	To Cor. to Secs. 11, 12, 13 & 14. Land; mountainous, 80 chs. Bunchgrass. Soil; 3rd rate.	
N. bet. Secs. 11 & 12.		
Var. 19° E.		
Ascend.		
10.00	Top of Ridge, course W. Descend.	+350
31.75	Gulch, course N.W.	-250
40.00	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable. Descend.	
80.00	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for Cor. to Secs. 1, 2, 11 & 12, marked with 5 notches on S. edge and 1 notch on E. edge. Raised mound of stone around it. Pits impracticable. Land; rough and mountainous, 80 chs. No timber, good grass. Soil; 2nd rate.	
E. on random line bet. Secs. 1 & 12.		
Var. $19^{\circ} 20'$ E.		
Set temp. $\frac{1}{4}$ Sec. Cor.		
79.80	Intersect Tp. line, 10 lks. S. of Cor. to Secs. 6, 7, 1 & 12.	