

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	ous, 40 chs. Thorn and willow in Creek bottom. Good grass.	
	N. bet. Secs. 34 & 35. Var. 9° 30' E.	
25.00	Summit, course E.	+150
40.00	Set basalt stone, 14 x 14 x 12 ins., 9 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised a mound of stone around it. Pits impracticable.	-150
80.00	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for Cor. to Secs. 26, 27, 34 & 35, marked with one notch on S. and 2 notches on E. edges. Raised a mound of stone around it. Pits impracticable.	
	Land; rough and mountainous, 80 chs.	
	Good bunch grass.	
	Soil; 3rd rate.	
	July 12, 1887.	
	E. on a random bet. Secs. 26 & 35. Var. 21° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.25	Intersect N. & S. line at Cor. to Secs. 25, 26, 35 & 36. Thence I run W. on a true line	
31.50	Summit.	+200
40.12	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised a mound of stone around it. Pits impracticable.	
42.35	Gulch, course N.	
46.35	" " "	
69.50	" " "	
75.00	Summit " "	
80.25	To Cor. to Secs. 26, 27, 34 & 35. Land; mountainous; sloping toward N. with sharp gulches. 80.25 chs.	-200
	Good bunch grass.	
	Soil; 2nd rate.	