

Subdivisional Lines, T.1 S., R.33 E., W. M.

Chains		Feet
76.50	Fence- enter field.	
80.00	Set post, 4 ft. long, 4 ins. sq., with marked stone, 12 ins. in ground, for Cor. to Secs. 2, 3, 10 & 11, marked T.1 S., R.33 E., S.11 on S.E., S.10 on S.W. faces, S.2 on N.E., S.3 on N.W. edges, with 2 notches on E. & 5 notches on S. Dug pits, 18x18x12 ins., N., E. & W. of post, 5½ ft. dist. & raised mound of earth, 2 ft. high, 4½ ft. base around post. Good bunch grass. No timber. Land; 2nd rate, rolling.	
	East on random line bet. Secs. 2 & 11. Var. 20°E.	
40.00	Set temp. ¼ Sec. Cor.	
80.10	Intersect N. & S. line, 10 lks. N. of Cor. to Secs. 1, 2, 11 & 12, Thence I run N. 89°56'W. on true line.	
20.25	Gulch, course N.	20
40.05	Set basalt stone, 12x10x8 ins., 8 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face. Raised mound of stone around it. Pits impracticable.	
50.25	Spring branch, 5 lks. wide; course N.	60
76.50	Enter field.	
80.10	Cor. to Secs. 2, 3, 10 & 11. Land; level. Soil; 1st rate. No timber, good grass.	
	N. on true line bet. Secs. 2 & 3. Var. 20°E.	
55.00	Leave field.	
9.00	McKay Creek, 50 lks. wide, course W.	
18.50	Leave creek bottom. Bluff of rock, 100 ft. high.	
40.00	Set basalt stone, 12 x 10 x 6 ins., 8 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face. Raised mound of stone around it. Pits impracticable.	
51.00	Top of ridge, course N.W.	400
73.50	Gulch, course S.W.	250
86.00	Intersect Base Line, 400 lks. W. of ¼ Sec. Cor. on S. Bdy. of Sec. 35. Set basalt stone, 10 x 10 x 8 ins., 6 ins. in ground, for Closing Cor. to Secs. 2 & 3, marked with	