

## Subdivisional lines, T. 1. S., R. 33 E., W.M.

Chains		Feet
	E. on a random bet. Secs. 28 & 33. Var. 19° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. & S. Edys at Cor to Secs. 27, 28, 33 & 34.	
	Thence I run	
	W. on a true line	
1.30	Gulch, course S.E.	- 20
30.00	Summit, course S.	+400
40.00	Set a basalt stone, 16 x 12 x 8 ins., 11 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	
77.50	Wagon Road, course N. & S.	
80.00	To Cor. to Secs. 28, 29, 32 & 33.	
	Land; mountainous, 80 chs.	
	Soil; 3rd rate.	
	Good grass.	
	N. bet. Secs. 28 & 29. Var. 19° E.	
7.25	Enter and leave road, course N. & S.	
31.39	Leave U.R. at 80th mile Cor., which is a basalt stone, 12 x 12 x 10 ins., 8 ins. in ground, marked U.R. 80 M. C.C. with mound of stone, over it.	
40.00	Set a basalt stone, 18 x 16 x 8 ins., 13 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	
80.00	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground for Cor. to Secs. 20, 21, 28 & 29, marked, 2 notches on S., and 4 notches on E. edges. Raised mound of stone a- round it. Pits impracticable.	
	Land; mountainous, 31.39 chs.	
	Soil; rocky, 4th rate. Very good grass.	
	July 17, 1887.	
	E. on random bet. Secs. 21 & 28. Var. 15° 45' E.	