

Subdivisional Lines, T. 1 S., R. 33 E., W.M.

Chains		Feet
	for Closing Cor. to Secs. 17 & 18, marked U.R. C.C. on N. face. Raised mound of stone around it. Pits impracticable.	
80.00	Set basalt stone, 10 x 10 x 8 ins., 6 ins. in ground, for Cor. to Secs. 17, 18, 19 & 20, marked, 3 notches on S., and 5 notches on E. edges. Raised mound of stone around Pits impracticable.	-150
	Land; mountainous, 63.50 chs.	
	Soil; rocky, 4th rate. Poor bunch grass.	
	W. on true line bet. Secs. 18 & 19	
	Var. 19° 30' E.	
10.00	Top of ridge	+300
19.00	Gulch, course S.	-100
37.50	Intersect U.R. Bdy. Set a basalt stone, 9 x 8 x 7 ins., 6 ins. in ground for Closing Cor., marked U.R. C.C. on W. face. Raised mound of stone alongside. Pits impracticable.	
40.00	Set basalt stone, 9 x 8 x 7, 6 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone alongside. Pits impracticable.	
45.00	Gulch, course N.W.	-100
55.00	Top of ridge N.	+200
76.00	Gulch, course N.	-100
135.25	Intersect Tp. line, 6.50 chs. S. of Cor. to Secs. 13 & 24. Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for Closing Cor., marked C.C. on E. face and 3 notches on N. & S. edges. Raised mound of stone alongside. Pits impracticable.	
	Land; mountainous, 97.75 chs.	
	Soil; 2nd rate. Poor grass.	
	W. on true line bet. Secs. 7 & 18.	
	Var. 19° 15' E.	
22.70	Gulch, course N.	-200
30.00	Summit, course N.	+150