

Subdivisiona T. 1 S., R. 33.E., W.M.

Chains		Feet.
	<p>From Closing Cor. to Secs. 17 and 18. on Res. Bdy., which is a basalt stone, 10 x 10 x 9 ins., in mound of stone and marked U.R.C.C. on N. face.</p> <p>I run----- Descend.</p> <p>S. bet. Secs. 17 & 18</p> <p style="text-align: right;">Var. 21° 00' E.</p>	
16.50	<p>Set a basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for Cor. to Secs. 17, 18, 19 & 20, marked, 5 notches on E. face, 3 notches on S. face and raised a mound of stone covered with earth, 2 ft. high, 4½ ft. base over it. Dug pits, 18 x 18 x 12 ins. in each Sec. Cor., 5½ ft. distant.</p> <p>Land; mountainous and stony, 16.50 chs.</p> <p>Soil; 4th rate. No timber.</p>	
	<p>E. on random line bet. Secs. 17 & 20.</p> <p style="text-align: right;">Var. 21° 15' E.</p> <p>Descend.</p>	
40.00	Set temp. ¼ Sec. Cor.	
79.20	<p>Intersect N. & S. line, 25 lks. S. of Cor. to Secs. 16, 17, 20 & 21, from which, I run</p> <p>S. 89° 49' W. on a true line bet. Secs. 17 & 20.</p> <p style="text-align: right;">Var. 21° 00' E.</p> <p>Descend.</p>	
39.60	<p>Set a basalt stone, 14 x 8 x 8 ins., 10 ins. in ground for ¼ Sec. Cor., marked ¼ on N. face; dug pits, 18 x 18 x 12 ins. E. & W. of Cor., and raised mound of earth, 2 ft. high, 4½ ft. base over it, on W. hillside.</p>	
54.70	Deep gulch, course S.W. Ascend.	
79.20	<p>The Cor. to Secs. 17, 18, 19 & 20.</p> <p>Land; mountainous and stony, 79.20 chs.</p> <p>Soil; 4th rate. No timber.</p>	
	<p>W. bet. Secs. 18 & 19.</p> <p style="text-align: right;">Var. 21° 15' E.</p> <p>Ascend stony ridge.</p>	