

## Subdivisions, T. 1 S., R. 33 E., W.M.

Chains		Feet
83.50	Summit falls N. Descend.	
116.40	Ravine, course N. Ascend.	
127.50	Summit of ridge falls N. Descend	400
131.00	Head of draw, course N.20° E.	
134.18	Intersect W. Bdy. of the Tp., 508 lks. S. of Cor. to Secs.	
	24 & 25, as set by me, and described on P. 19 of these notes.	
	At point of intersection, I	
	Set basalt boulder, 12 x 8 x 6 ins., 12 ins. in ground for	
	Closing Cor. to Secs. 19 & 30, marked, 6 notches and 60°	
	on E. face, and 2 notches on S. face; dug pits, 18 x 18	
	x 12 ins., N., S. and E. of stone, by which, I deposit a	
	flat pint flask, and raised mound of earth, 2 ft. high	
	a 4½ ft. base over Cor., on gentle N.E. slope.	
	Soil; 3rd & 4th rates. No timber.	
	Mountainous, 134.18 chs.	
	Var. 18° 30' E.	
	N. on a random line bet. Secs. 19 & 20.	
	Var. 19° 45' E.	
5.00	Summit of ridge, falls W. Descend.	
40.00	Set temp. ¼ Sec. Cor.	
78.35	Intersect E. & W. line, 200 lks. W. of Cor. to Secs. 17, 18,	
	19 & 20. (See note on pg. 12).	
	Thence I run,	
	S. 1° 26' W. on a true line bet. Secs. 19 & 20.	
	Var. 21° 15' E.	
	Descend.	
9.25	Wagon Road brs. E. & W.	
9.35	Enter field, fence E. & W.	
10.73	Steward Creek, 25 lks. wide, runs W. Enter brush.	
11.73	Leave brush.	
18.35	Summit of ridge falls N.W. Descend.	
20.35	Ravine, course N.W. Ascend.	
30.06	Leave field.	
39.18	Set basalt stone, 18 x 10 x 4 ins., 12 ins. in ground for	