

Subdivisions, T. 1 S., R. 33 E., W.M.

Chains		Feet
	<p>$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; dug pits, 18 x 18 x 12 ins., N. & S. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth and stone, $2\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor., on N. hillside.</p>	
44.85	Stony summit falls W. Descend	400
62.60	Deep ravine, course N.W. Ascend.	
73.35	Summit of ridge, falls W. Descend.	
78.35	<p>The Cor. to Secs. 19, 20, 29 & 30.</p> <p>Land; mountainous and stony, 35 chs.; hilly and rolling, 32.35 chs.</p> <p>Soil; 5th rate.</p> <p>Brush, cottonwood & cherry, 11.00 chs.</p> <p>No timber, except scattering cottonwood on Steward Creek.</p> <p style="text-align: right;">Sept. 16, 1890.</p>	
General Description		
<p>The land in this Tp. embraced in my Contract No. 551, is, in general, mountainous and hilly.</p> <p>The soil is of 3rd and 4th rate grades, excepting along Steward Creek, where there are spots of rich land.</p> <p>Good mountain bunch grass is found on N. & E. slopes.</p> <p>Timber, scarce, consisting of pine, fir, quakenasp and cottonwood.</p> <p>There are five settlers in Sec. 19, two in Sec. 30 and one in Sec. 20, most of whom, have good houses and other improvements of permanent character, having occupied their claims for many years.</p> <p>The magnetic declination varies from 13° E. to $25^{\circ} 30'$ E. and does not appear to remain constant at any particular point.</p>		
<p>Note:</p> <p>I built mounds "over" Cors. instead of alongside, for the reason that I believed it to be the better plan to securely preserve the true Cor. point, since the mound thus formed would tend to prevent the Cor. stone being rolled or washed away on steep ground.</p>		