

Subdivisional Allotments, T. 1 S., R. 33 E., W.M.

Section 4:

Chains		Feet
20.00	Set temp. 1/16 Sec. Cor.	
40.00	Intersect the E. Bdy. at 1/16 Sec. Cor., 20.00 chs. N. of the Cor. to Secs. 3, 4, 9 & 10, Thence I run, W. on a true line in Sec. 4 Var. 19° E.	
20.00	Set post, 3 ft. long, 3 ins. sq., with charred stake, 12 ins. in ground for 1/16 Sec. Cor., marked 1/16 S. on N. face; dug pits, 18 x 18 x 12 ins., E. & W. of post, 5½ ft. dist. and raised mound of earth, 1½ ft. high, 3½ ft. base around post.	
30.00	McKay Creek, 20 lks. wide, course N. 10° W.	
40.00	To 1/16 Sec. Cor. Land in rich bottom. Soil; gravelly 1st and 2nd rate.	
	From the ½ Sec. Cor. bet. Secs. 4 & 9. I run, E. on true line bet. Secs. 4 & 9. Var. 19° E.	
11.75	Gulch, course N.	
19.95	Deposited charred stake 12 ins. in ground for 1/32 Sec. Cor. dug pits, 18 x 18 x 12 ins., E. & W. of stake, 5½ ft. dist. and raised mound of earth, 1½ ft. high, 3½ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. sq., 12 ins. in ground, marked 1/32 S. on N. face.	
24.60	Gulch, course N.	
39.90	The Cor. to Secs. 3, 4, 9 & 10., which is a post 4 ft. long 4 ins. sq., marked with 5 notches on S. and 3 notches on E. edges and T.1 S., S.3 on N.E. S.10 on S.E. S.9 on S.W. R.33 E., S. 4 on N.W. faces; pits 18 x 18 x 12 ins. in each Sec. 5½ ft. dist. and mound of earth, 4 ft. base around it. I marked post D.R. on N. face.	