

Subdivisional Allotments, T.1 S., R.33 E., W.M.
Section 5

Chains		Feet
	<p>From the 1/32 Sec. Cor., 10.00 chs. S. of the 1/4 Sec. Cor. bet. Secs. 5 & 6.</p> <p>I run E. on a true line in Sec. 5.</p> <p style="text-align: right;">Var. 20° E.</p>	
14.25	Gulch, course N.	
20.00	<p>Set stone, 9 x 8 x 7 ins., 6 ins. in ground for 1/16 Sec. Cor., marked 1/16 on N. face; dug pits, 18 x 18 x 12 ins., E. & W. of Cor., 5 1/2 ft. dist. and raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p>	
30.00	Fence, N.350 lks., turns to N.	
35.50	Gulch, course N.	50
40.00	<p>Set stone, 13 x 8 x 6 ins., 8 ins. in ground for 1/16 Sec. Cor., marked 1/16 on N. face; dug pits, 18 x 18 x 12 ins. E. & W. of Cor., 5 1/2 ft. dist. Raised mound of earth, 1 1/2 ft. high, 3 1/2 ft. base over stone.</p> <p>Line on N. face of mountain. Soil; 1st rate.</p>	
	<p>From the 1/16 Sec. Cor., 10.00 chs. S. and 40 chs. E. of 1/4 Sec. Cor. bet. Secs. 5 & 6.</p> <p>I run N. on true line in Sec. 5.</p> <p style="text-align: right;">Var. 19° 30' E.</p>	
8.50	Foot of hill.	
14.50	Road, course E. & W.	
20.00	<p>Set stone, 8 x 8 x 8 ins., 5 ins. in ground for 1/16 Sec. Cor., marked 1/16 on W. face; dug pits, 18 x 18 x 12 ins. N. & S. of stone, 5 1/2 ft. dist. and raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p> <p>Land; mountain slopes to the N. and creek bottom. Soil; 1st & 2nd rate, gravelly. Sumach and other brush in creek bottom.</p>	
	June 24, 1889.	