

Subdivisional Allotments, T. 1 S., R. 33 E., W.M.
Section 5.

Chains	Feet
	From the 1/16 Sec. Cor., 40 chs. E. and 10 chs. N. of the $\frac{1}{4}$ Sec. Cor., bet. Secs. 5 & 6, I run W. on random line in Sec. 5. 20.00 Var. $19\frac{1}{2}^{\circ}$ E. 20.00 Set temp. 1/16 Sec. Cor. 40.00 Intersect the W. line at a point 8 lks. S. of the 1/16 Sec. Cor. bet. Secs. 5 & 6. Thence I run, S. $89^{\circ} 53'$ E. on a true line in Sec. 5. Var. $16^{\circ} 45'$ E. Along creek bottom. 16.00 Leave brush. 20.00 Set stone, 10 x 8 x 7 ins., 7 ins. in ground for 1/16 Sec. Cor., marked 1/16 on N. face; dug pits, 18 x 18 x 12 ins. E. & W. of stone $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. 22.50 Indian house. 40.00 To the 1/16 Sec. Cor. Land; level creek bottom. Soil; 1st rate and gravelly. Scattering sumach brush and grain. June 24, 1889
	<u>Section 6</u>
	From the 1/16 Sec. Cor. 10 chs. N. of the $\frac{1}{4}$ Sec. Cor., bet. Secs. 5 & 6, I run W. on a true line in Sec. 6 Thru timber & undergrowth. Var. $16^{\circ} 45'$ E. 19.80 Slough, course, S.W., water in holes. 20.00 A willow, 4 ins. diam., which I mark 1/16 on S. face for 1/16 Sec. Cor., from which, A cherry, 5 ins. diam., brs. W. 25 lks. dist., marked 1/16 S. B.T.