

T. 1 S., R. 34 E., W.M.

Chains		Feet
	marked $\frac{1}{4}$ S., B.T.	
	A pine, 16 ins. diam., brs. S. 55° E., 42 lks. dist., marked $\frac{1}{4}$ S., B.T.	
62.00	Summit of ridge	+300
74.00	Gulch, course S.E.	- 50
80.00	Set a post, 48 x 4 x 4 ins., 24 ins. in ground for Cor. to Secs. 4, 5, 32 & 33, marked T.1 S., S.32 on N.W. R.34 E., S.33 on N.E. T.2 S., S.4 on S.E. S 5 on S.W., 4 notches on E. and 2 on W. edges, from which, A pine, 6 ins. diam., brs. S.45° W., 60 lks. dist., marked, T.2 S., R.34 E., S.5, B.T. A pine, 10 ins. diam., brs. N.40° E., 58 lks. dist., marked T.1 S., R.34 E., S.33, B.T. A pine, 20 ins. diam., brs. N. 5° W., 32 lks. dist., marked S.32, B.T. Land; mountainous, 80.00 chs. Timber; in canyons, scattering pine. Good bunch grass. Soil; 4th rate.	
	S. 89° 25' W. on S. Bdy. Sec. 32 Var. 21° 20' E:	
6.00	Gulch, course N.E.	- 60
26.50	Summit, course N.	+800
40.00	Set basalt stone, 12 x 12 x 5 ins., 8 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone alongside. Pits impracticable.	
69.00	Canyon, course N.W.	-300
73.00	Top of ridge, course N.	-400
80.00	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground for Cor. to Secs. 5, 6, 31 & 32, marked 5 notches on E. and one notch on W. edges. Raised mound of stone alongside. Pits impracticable. Land; mountainous, 80.00 chs.	