

T. 1 S., R. 34 E., W.M.

Chains		Feet
	<p>Good bunch grass; No timber anyons. Soil; 3rd rate. June 25, 1887.</p>	
	<p>S. 89° 25' W. on S. Bdy. of Sec. 31 Var. 19° E.</p>	
9.75	Gulch, course N.	75
19.00	Ledge of rock, course N.	50
20.50	Spring branch, 5 lks. wide, c. N.	50
36.00	Top of ridge, course N.	600
40.00	<p>Set a basalt stone, 10 x 8 x 8 ins., 7 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone alongside. Pits impracticable.</p>	300
42.25	Canyon, course N.	40
56.00	Top of ridge, course N.	400
82.70	<p>To Cor. to Tps. 1 & 2 S., Rs. 33 & 34 E. Land; mountainous, 80.00 chs. Scattering pine timber in canyons. Soil; 3rd rate. June 25, 1887.</p>	
	<p>I now return to Cor. to Tps. 1 & 2 S., Rs. 34 & 35 E. and Run thence N. on true line on E. Bdy. of Sec. 36, Tp. 1 S., R. 34 E. Var. .20° 30' E.</p>	
	<p>Descend along E. side of ridge. Very rocky with high cliffs.</p>	
40.00	<p>Set basalt stone, 10 x 8 x 7 ins., 7 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone alongside. Pits impracticable.</p>	
55.50	Creek, course N.W., 1 lk. wide	600
80.00	<p>Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground for Cor. to Secs. 25, 30, 31 & 36, marked one notch on S. and 5 on N. edges. Raised mound of stone alongside. Pits impracticable.</p>	
	<p>Land; mountainous, 80.00 chs.</p>	