

T. 1 S., R. 34 E., W.M.

Chains		Feet
	Soil; 5th rate. Timber; pine and fir, scattering in canyons.	
	N. on E. Bdy. of Sec. 25. Var. 17° E.	
3.00	Top of ridge, course N.W.	+100
7.00	Gulch, course N.W.	-100
33.00	Bluff of rock	+100
36.15	McKay creek, 15 lks. wide, W.	-200
40.00	Set basalt stone, 12 x 9 x 8 ins., 8 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone alongside. Pits impracticable.	
80.00	Set basalt stone, 14 x 8 x 9 ins., 9 ins. in ground for Cor. to Secs. 19, 24, 25 & 30, marked two notches on S. and 4 notches on N. edges. Raised mound of stone alongside. Pits impracticable.	
	Land; mountainous, 80.00 chs. Timber; scattering pine, fir and tamarack in canyons. Good bunch grass. Soil; 3rd rate.	
	N. on E. Bdy. of Sec. 24. Var. 22° E.	
30.00	Top of mountain	+200
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on W. face, from which, A pine, 12 ins. diam., brs. S. 42° W., 36 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 24 ins. diam., brs. S. 84° E., 99 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.00	Set basalt stone, 20 x 10 x 10 ins., 15 ins. in ground, for Cor. to Secs. 13, 18, 19 & 24, marked 3 notches on N. & S. edges from which, A pine, 16 ins. diam., brs. N. 70° E., 127 lks. dist., marked T.1 S., R.35 E., B.T.	