

T. 1 S., R. 34 E., W.M.

| Chains |  | Feet |
|--------|--|------|
|        | <p>marked <math>\frac{1}{4}</math> S. B.T.</p> <p>A fir, 12 ins. diam., brs. N.80° E., 21 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S., B.T.</p>   |      |
| 50.00  | Enter underbrush.  |      |
| 80.00  | <p>Set post, 48 x 4 x 4 ins., 2 ft. in ground, for Cor. to<br/>Secs. 1, 6, 7 &amp; 12, marked,</p> <p>T. 1 S., S. 1 on N.W.<br/>R. 34 E., S. 12 on S.W.<br/>S. 6 on N.E.<br/>R. 35 E., S. 7 on S.E. faces</p> <p>with 5 notches on S. and 1 notch on N. edges, from which,<br/>which,</p> <p>A fir, 12 ins. diam., brs. S. 80° E., 21 lks. dist.,<br/>marked T. 1 S., R. 35 E., S. 7, B.T.</p> <p>A pine, 16 ins. diam., brs. N. 80° W., 21 lks. dist.,<br/>marked R. 34 E., S. 1, B.T.</p> <p>No other trees in limits. Pits impracticable.</p> <p>Land; level<br/>Soil; 2nd rate.<br/>Timber; pine, fir and tamarack with dense underbrush, 80.<br/>chs.</p> |      |
|        | <p>N. on E. Bdy. Sec. 1</p> <p>Var. 19° E.</p>   |      |
| 16.00  | Descend.   |      |
| 26.00  | Branch, 10 lks. wide, course N.W.  | -500 |
| 32.00  | Top of hill.   | +600 |
| 40.00  | <p>Set charred post, 36 x 3 x 3 ins., 2 ft. in ground, for <math>\frac{1}{4}</math><br/>Sec. Cor., marked <math>\frac{1}{4}</math> S. on W. face, from which,</p> <p>A fir, 12 ins. diam, brs. N. 88° E., 175 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A pine, 20 ins. diam., brs. N. 70° W., 192 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S., B.T.</p>  |      |
| 61.50  | Bed of creek, water in holes   | -800 |
| 82.90  | <p>Intersect Base Line, 5.93 chs. W. of <math>\frac{1}{4}</math> Sec. Cor. on S. Bdy.<br/>of Sec. 31, T. 1 N., R. 35 E.</p>  |      |