

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
68.80	Canyon, N.W.	
80.00	Set basalt stone, 20 x 14 x 4 ins., 15 ins. in ground, for Cor. to Secs. 25, 26, 35 & 36, marked 1 notch on S. and E. edges. Raised mound of stone around it. Pits impracticable.	
	Land; mountainous, 80.00 chs.	
	Soil; 3rd rate.	
	Scattering tamarack in canyon.	
<hr/>		
	E. on random bet. Secs. 25 & 36.	
	Var. 18° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersect N. & S. line, 70 lks. S. of Cor. to Secs. 25 & 36.	
	Thence I run	
	S.89° 30' W. on true line.	
15.00	Canyon and brook, 5 lks. wide, course N.	-800
27.00	Ridge, course N.E.	+200
28.50	Point, N.E.	+ 50
40.10	Set basalt stone, 20 x 12 x 8 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face. Raised mound of stone around it. Pits impracticable.	
47.50	Gulch, course N.	-150
67.50	Summit of ridge, N.	+600
80.20	To Cor. to Secs. 25, 26, 35 & 36.	
	Land; mountainous, 80.00 chs.	
	Soil; rocky, 4th rate.	
	Scattering timber in canyon. Some bunch grass.	
<hr/>		
	N. bet. Secs. 25 & 26.	
	Var. 18° 30' E.	
20.00	Summit of ridge	+300
40.00	Set basalt stone, 20 x 10 x 10 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around it. Pits impracticable.	
52.50	McKay Creek, 10 lks. wide, course W.	-800