

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
	N. bet. Secs. 26 & 27.	
	Var. 21° 45' E.	
	Descend E. side of canyon.	
40.00	Set basalt stone, 10 x 10 x 6 ins., 6 ins. in ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around it. Pits impracticable.	
43.25	Mouth of canyon, course W.	
80.00	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, marked 2 notches on S. and 2 notches on E. edges, for Cor. to Secs. 22, 23, 26 & 27. Raised mound of stone around it. Pits impracticable.	
	Land; rough, mountainous, 80.00 chs. Bunch grass.	
	Soil; 3rd rate.	
<hr/>		
	E. on random bet. Secs. 23 & 26.	
	Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersect N. & S. line, 40 lks. N. of Cor. to Secs. 23, 24, 25 & 26.	
	Thence I run, N. 89° 43' W. on a true line.	
5.00	Top of ridge, course S.	+800
40.10	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around it. Pits impracticable.	
42.50	McKay Creek, 20 lks. wide, course N.W.	-1000
64.00	Top of sharp ridge, course N.W.	+800
80.20	To Cor. to Secs. 22, 23, 26 & 27.	-300
	Land; rough and mountainous, 80.20 chs.	
	Pine timber in canyons.	
	Some bunch grass.	
	Soil; 3rd rate.	
<hr/>		
	N. bet. Secs. 22 & 23.	
	Var. 21° E.	
7.50	Summit of ridge	+400