

Subdivisional Lines, T. 1 S., R.34 E., W.M.

Chains		Feet
15.00	Descend bluff	
20.50	McKay Creek, 25 lks. wide, course W.	-400
40.00	Set basalt stone, 36 x 24 x 24 ins., 27 ins. in ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ Sec. Cor. stone. Sets on E. side of cliff.  Pine tree, 18 ins. diam., brs. N.70° E., 145 lks. dist. marked $\frac{1}{4}$ S., B.T.  No other trees in limits Raised mound of stone around it.  Pits impracticable.	
51.00	Gulch, course S.W.	-100
76.50	" " "	-100
80.00	Set basalt stone, 14 x 12 x 12 ins., 9 ins. in ground, for Cor. to Secs. 14, 15, 22 & 23, marked, 3 notches on S., 2 notches on E. edges. Raised mound of stone around it.  Pits impracticable.  Land; mountainous, 80 chs.  Timber; on creeks, good bunch grass.  Soil; 3rd rate.	
E. on random bet. Secs. 14 & 23.  Var. 19° E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. & S. line, 33 lks. N. of Cor. to Secs. 13, 14, 23 & 24.  Thence I run, N.89° 46' W. on true line.  Descend.	
8.00	Canyon, course S.W. Descend.	-600
27.00	Ridge, course S.	+600
30.00	Gulch, course S.	-200
40.00	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, marked $\frac{1}{4}$ on N. face for $\frac{1}{4}$ Sec. Cor. Raised mound of stone around it. Pits impracticable.	
59.00	Top of ridge	+800
77.00	Creek, with water in holes	-600