

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
80.00	To Cor. to Secs. 14, 15, 22 & 23. Land; rough and mountainous, 80 chs. No timber. Good bunch grass. Soil; 4th rate.	
	N. bet. Secs. 14 & 15. Var. 19° E.	
32.00	Top hill	+1000
40.00	Set post, 3 ft. long, 3 ins. sq., 2 ft. in ground, marked $\frac{1}{4}$ S. on W. face, for $\frac{1}{4}$ Sec. Cor., from which, A pine, 10 ins. diam., brs. S. 40° E., 70 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 12 ins. diam., brs. S. 60° W., 53 lks. dist., marked $\frac{1}{4}$ S., B.T.	
59.00	Canyon, course W.	-600
69.50	Top of ridge	+500
80.00	Set basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for Cor. to Secs., 10, 11, 14 & 15, marked 4 notches on S., 2 notches on E. edges. Raised mound of stone around it, pits impracticable. Land; rough and mountainous, 80 chs. Pine timber in canyons. Bunch grass. Soil; 3rd rate.	+400
	E. on random line bet. Secs. 11 & 14. Var. 20° 45' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.75	Intersect N. & S. line, 40 lks. S. of Cor. to Secs. 11, 12, 13 & 14. Thence I run, S. 89° 43' W. on true line	
39.87	Set basalt stone, 10 x 8 x 8 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	
48.00	Ravine, course N.	-200