

Subdivisional lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
51.00	Top of hill	+250
58.00	Descend.	
79.75	To Cor. of Secs. 10, 11, 14 & 15.	
	Land; mountainous on last 39.88 chs.; remainder, rolling. Scattering pine timber, bunch grass. Soil; 2nd rate.	
	N. bet. Secs. 10 & 11.	
	Var. 20° 45' E.	
11.00	Dry branch, course S.W.	-300
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for ¼ Sec. Cor., marked ¼ S. on W. face, from which, A fir, 6 ins. diam., brs. N. 30° E., 5 lks. dist., marked ¼ S., B.T. A fir, 6 ins. diam., brs. S. 25° W., 46 lks. dist. marked ¼ S., B.T.	
42.25	Dry branch, course S.W.	-100
56.00	Top of ridge, course W.	+200
65.50	Branch (dry), course S.W.	-150
80.00	Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, for Cor. to Secs. 2, 3, 10 & 11, marked, T.1 S., S.2 on N.E. S.3 on N.W. R.34 E., S.10 on S.W. 'S.11 on S.E.' 5 notches on S. edge 2 notches on E. edge, from which, A pine, 18 ins. diam., brs. N.40° E., 91 lks. dist., marked T.1 S., S. 2, B.T. A pine, 14 ins. diam., brs. S.20° E., 85 lks. dist., marked T.1 S., R.34 E., S.11, B.T. A pine, 16 ins. diam., brs. S.83° W., 109 lks. dist., marked T.1 S., R.34 E., S.10, B.T. A pine, 24 ins. diam., brs. N. 54° W., 108 lks. dist., marked T.1 S., R.34 E., S.3, B.T.	