

## Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
	also	
	A pine, 18 ins. diam., brs. S.10° E., 43 lks. dist., marked $\frac{1}{4}$ S., B.T.	
45.00	Creek, 20 lks. wide, course N.	-600
79.50	To Cor. to Secs. 21, 22, 27 & 28. Land; rough and mountainous, 79.50 chs. Scattering pine timber. Soil; 3rd rate.	
<hr/>		
	N. bet. Secs. 21 & 22. Var. 19° 30' E.	
2.00	McKay Creek, 25 lks. wide, course W.	-100
9.00	Leave Creek bottom, ascend.	
34.50	Bluff of rock, 15 ft. high.	
40.00	Set basalt stone, 10 x 10 x 7 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	+900
45.00	Top of ridge, course S.W.	+450
67.25	Creek, course S.W., 10 lks. wide	-800
80.00	Set basalt stone, 12 x 12 x 8 ins., 8 ins. in ground, for Cor. to Secs. 15, 16, 21 & 22, marked, 3 notches on S. and 3 notches on E. edges. Raised mound of stone a- round it. Pits impracticable.	+200
	Land; rough and mountainous, 80 chs. Good bunch grass. Soil; 3rd rate.	
<hr/>		
	E. on random bet. Secs. 15 & 22. Var. 19° 20' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. & S. line, 70 lks. S. of Cor. to Secs. 14, 15, 22 & 23. Thence I run S.89° 30' W. on true line	
26.00	Canyon, course S.W.	*800
40.00	Set basalt stone, 16 x 12 x 8 ins., 10 ins. in ground, for	