

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
	$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	+900
	Descend	
60.50	Creek, 10 lks. wide, course S.W.	+800
80.00	To Cor. to Secs. 15, 16, 21 & 22 Land; rough and mountainous, 80 chs. Good bunch grass. Soil; 3rd rate.	
	N. bet. Secs. 15 & 16.	
	Var. 19° 20' E.	
	Ascend.	
15.00	Top of ridge	+800
40.00	Set basalt stone, 20 x 16 x 12 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raise mound of stone around it. Pits impracticable.	
75.00	Enter scattering pine timber.	
80.00	Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, for Cor. to Secs. 9, 10, 15 & 16, marked T.1 S., S.10 on N.E. R.34 E., S.15 on S.E. S.16 on S.W. S.9 on N.W. 3 notches on E. edge and 4 notches on S. edge, from which, A pine, 18 ins. diam., brs. N.40° E., 127 lks. dist. marked T.1 S., R.34 E., S.10, B.T. A pine, 16 ins. diam., brs. S.77° E., 77 lks. dist., marked S.15, B.T. Also A pine, 14 ins. diam., brs. S.77° W., 67 lks. dist., marked T.1 S., R.34 E., S.16, B.T. A pine, 12 ins. diam., Brs. N.67° W., 78 lks. dist., marked T.1 S., R.34 E., S.9, B.T. Land; mountainous, 80 chs. Bunch grass. Soil; 3rd rate.	