

Subdivisional Lines, T. 1. S., R. 34 E., W.M.

Chains		Feet
	E. on random bet. Secs. 28 & 33.	
	Var. 20° 45' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersect N. & S. line at Cor to Secs. 27, 28, 33 & 34.	
	Thence I. run	
	W. on a true line.	
26.50	Summit of ridge, course N.	+800
40.10	Set basalt stone, 10 x 8 x 7 ins., 6 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	-200
47.50	Head of canyon, course N.W.	-200
67.50	Ridge, course N.W.	+200
70.00	Canyon, course N.	-800
80.20	To Cor. to Secs. 28, 29, 32 & 33.	
	Land; rough and mountainous, 80.20 chs.	
	Covered with bunch grass.	
	Soil: 3rd rate.	
	N. bet. Secs. 28 & 29.	
	Var. 20° 45' E.	
40.00	Set basalt stone, 12 x 10 x 8 ins. 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, A pine, 4 ins. diam., brs. N. 25° E., 75 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 12 ins. diam., brs. S. 53 lks. dist., marked $\frac{1}{4}$ S., B.T.	
56.00	McKay Creek, 20 lks. wide, course W.	-300
80.00	Set basalt stone, 18 x 12 x 10 ins., 14 ins. in ground, for Cor. to Secs. 20, 21, 28 & 29, marked, 2 notches on S. & 4 notches on E. edges. Raised mound of stone around it. Pits impracticable.	+400
	Land; broken and mountainous, 80 chs.	
	Pine timber on Creek bottom.	
	Bunch grass on hills.	
	Soil; 3rd rate.	