

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
	<p>around it. Pits impracticable.</p> <p>Land; mountainous and rocky, 85.00 chs.</p> <p>Pine timber in canyons.</p> <p>Some bunch grass.</p> <p>Soil; 4th rate.</p>	
	<p>From the Cor. to Secs. 5, 6, 31 & 32, on S. Bdy. of Tp. N. bet. Secs. 31 & 32.</p> <p style="text-align: center;">Var. 20° E.</p>	
10.25	Canyon, course N.W.	-400
16.00	Summit, course N.W.	+300
25.00	Canyon, course N.W.	-250
33.00	Summit, course W.	+250
40.00	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face. Raised mound of stone ground it. Pits impracticable.	
80.00	Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, for Cor. to Secs. 29, 30, 31 & 32, marked, T.1 S., S.29 on N.E. S.30 on N.W. R.34 E., S.31 on S.W. S. 32 on S.E. faces with 1 notch on S. and 5 notches on E. edges, from which A pine, 10 ins. diam., brs. N.30° E., 48 lks. dist. marked T.1 S., R.34 E., S.29, B.T. A pine, 8 ins. diam., brs. S.60° W., 20 lks. dist., marked T.1 S., R.34 E., S.31, B.T. No other tree in limits. Raised mound of stone around it. Pits impractic- able.	
	<p>Land; mountainous, 80 chs.</p> <p>Scattering timber.</p> <p>Soil; 2nd rate.</p>	
	<p>E. on random bet. Secs. 29 & 32.</p> <p style="text-align: center;">Var. 20° E.</p>	