

Subdivisional Lines, T. 1 S., R. 34 E., W. M.

Chains		Feet
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. & S. line, 80 lks. S. of Cor. to Secs. 28, 29, 32 & 33. Thence \bar{I} run S. $89^{\circ} 26'$ W on true line	
12.50	Summit, course N.	+400
36.20	Canyon, course N.	-500
40.00	Set basalt stone, 30 x 20 x 15 ins., 22 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, Raised mound of stone around it. Pits impracticable.	
60.00	Summit, course N.	+400
75.00	Gulch, course N.W.	-300
80.00	To Cor. to Secs. 29, 20, 31 & 32. Land; rough and mountainous, 80 chs. Good bunch grass. Soil; rocky, 2nd rate.	
W. on random bet. Secs. 30 & 31. Var. 20° E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
82.70	Intersect Tp. line, 80 lks. N. of Cor. to Secs. 25, 30, 31 and 36. Thence \bar{I} run N. $89^{\circ} 27'$ E. on true line.	
42.70	Set post, 36 x 3 x 3 ins., 24 ins. in ground, for $\frac{1}{4}$ Secs. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A pine, 24 ins. diam., brs. S. 72° E., 206 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 4 ins. diam., brs. N. 50° W., 109 lks. dist., marked $\frac{1}{4}$ S., B.T.	
82.00	Canyon, course N.	-200
82.70	To Cot. to Secs. 29, 20, 31 & 32. Land; rough and mountainous, 82.70 chs. Good bunch grass. Soil; 3rd rate.	
N. bet. Secs. 29 & 30. Var. 20° E.		