

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
	Raised mound of stone around it. Pits impracticable.	-200
59.20	McKay Creek, 15 lks. wide, course N.	-200
68.45	Leavet Creek Bottom.	
82.45	To Cor. to Secs. 19, 20, 29 & 30.	+300
	Land; mountainous, 82.45 chs.	
	Good pine and cottonwood timber on bottom.	
	Soil; On W. side of Creek, 1st rate- On E. side, 4th rate.	
<hr/>		
	N. bet. Secs. 19 & 20.	
	Var. 21° 45' E.	
30.00	Summit ridge, course W.	+250
40.00	Set a basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face. Raised mound of stone around it. Pits impracticable.	
48.50	Gulch, course W.	- 50
59.00	Ridge	+150
80.00	Set basalt stone, 14 x 10 x 8 ins., 9 ins. in ground, for Cor. to Secs. 17, 18, 19 & 20, marked, 3 notches on S. and 5 notches on E. edges. Raised mound of stone around it. Pits impracticable.	
	Cor. in Gulch, course W.	-150
	Land; mountainous and broken.	
	No timber, good bunch grass.	
	Soil; 3rd rate.	
<hr/>		
	E. on random bet. Secs. 17 & 20.	
	Var. 21° 30' E.	
40.00	Set temp. ¼ Sec. Cor.	
79.80	Intersect N. & S. line at Cor. to Secs. 16, 17, 20 & 21. Thence I run W. on true line.	
118.55	Canyon, course S.	- 50
14.10	Gulch, course S.	
30.00	Summit of ridge, course S.	+ 40
39.90	Set basalt stone, 10 x 8 x 6 ins., 6 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face. Raised mound of stone around it. Pits impracticable.	