

Subdivisional Lines, T. 1 S., R. 34 E., W.M.

Chains		Feet
43.00	Canyon, course S.	-200
55.00	Summit, course S.	+400
79.80	To Cor. to Secs. 17, 18, 19 & 20. Land; rough and mountainous, 79.80 chs. No timber, poor bunch grass. Soil; 3rd rate. July 7th, 1887.	
	W. on random bet. Secs. 18 & 19. Var. 21° 30' E.	
110.00	Set temp. $\frac{1}{4}$ Sec. Cor;	
82.70	Intersect Tp. line, 75 lks. N. of Cor. to Secs. 13, 18, 19 and 24. Thence I run, N. 89° 29' E. on true line	
32.95	McKay Creek, 20 lks. wide, course N.	-400
42.70	Set basalt stone, 12 x 8 x 7 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone around it. Pits impracticable.	
82.70	To Cor. to Secs. 17, 18, 19 & 20. Land; mountainous, 82.70 chs. Good timber on W. half. Soil; 3rd rate.	
	N. bet. Secs. 17 & 18. Var. 21° 30' E.	
144.00	Summit, course W.	+300
24.25	Gulch, course W.	-200
30.75	Gulch, course W.	- 50
40.00	Set basalt stone, 12 x 9 x 7 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone around it. Pits impracticable.	+100
49.50	Summit, course W.	+200
80.00	Cor. to Secs. 7, 8, 17 & 18, marked 4 notches on S. and 5 notches on E. edges. Raised mound of stone around it.	- 80