

Resurvey Portion N. Bdy., T. 2 S., R. 34 E., W.M.

Chains	Feet										
	N.89°35'E., continuing my measurements.										
	Ascend 60 ft. to										
45.20	Top of spur, slopes S.W.; along steep S. slope.										
55.70	Dry gulch, course S.W.; ascend 775 ft. to										
80.00	Set iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground for Cor. of Secs. 1 & 2, with brass cap marked,										
	<table border="1"> <tr><td colspan="2">T1SR34E</td></tr> <tr><td colspan="2">S35</td></tr> <tr><td>S2</td><td>S1</td></tr> <tr><td>T2S</td><td>R34E</td></tr> <tr><td colspan="2">1917</td></tr> </table>	T1SR34E		S35		S2	S1	T2S	R34E	1917	
T1SR34E											
S35											
S2	S1										
T2S	R34E										
1917											
	and raise mound of stone, 4 ft. base, 2 ft. high, S. of Cor.										
	Land; mountainous.										
	Soil; rocky, 3rd rate.										
	Timber; fir and pine.										
	Undergrowth; fir, ninebark and willow.										
<hr/>											
	N.89° 35' E., resurveying the N. Bdy. of Sec. 1.										
	Over mountainous land; ascend 25 ft. to										
1.62	Intersect the point for Cor. of Secs. 1, 2, 35 & 36, in a crib of rock, 4 x 4 x 4 ft., built as an anchor for fences, extending N., E. & N.W. This Cor. point was pointed out by L.S. Kidd, who claims to have known its location ever since the original survey was made. At a point, 6 lks. N. of the Cor., thus determined, Set iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground for witness Cor. to the Cor. of Secs. 35 & 36, with brass cap marked,										
	<table border="1"> <tr><td>T1S</td><td>R34E</td></tr> <tr><td>S35</td><td>S36</td></tr> <tr><td colspan="2">T2SR34E</td></tr> <tr><td colspan="2">WC</td></tr> <tr><td colspan="2">1917</td></tr> </table>	T1S	R34E	S35	S36	T2SR34E		WC		1917	
T1S	R34E										
S35	S36										
T2SR34E											
WC											
1917											
	A crib of rock, 4 x 4 x 4 ft., brs. S. of post, 6 ft. dist.										
	Thence										
	S.84° 15' E., continuing my measurements.										
	Along fence										
11.60	Top of ridge, brs. N.W. & S.E.; descend 310 ft. to										