

Resurvey Portion N. Bdy. T.2 S., R. 34 E., W.M.

| Chains | | Feet |
|--------|---|------|
| 22.90 | Dry gulch, course N.W.; ascend 200 ft. to | |
| 39.80 | Intersect the old $\frac{1}{4}$ Sec. Cor., which is a basalt stone, | |
| | 10 x 8 x 7 ins., set in small mound of stone, marked | |
| | $\frac{1}{4}$ on N. face. | |
| | At a point, 1 lk. N. of Cor: | |
| | Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, | |
| | for witness Cor. to the $\frac{1}{4}$ Cor. of Secs. 36 only, with | |
| | brass cap marked, | |
| | <u>1836</u> | |
| | WC | |
| | 1917 | |
| | From true Cor. | |
| | A pine, 48 ins. diam., brs. N.8°15'E., 173 lks. dist., | |
| | marked $\frac{1}{4}$ S.36, B.T. | |
| | Thence | |
| | N.83°19'E., continuing my measurements. | |
| 40.19 | (40.00 chs. departure) | |
| | Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, | |
| | for $\frac{1}{4}$ Cor. of Sec. 1 only, with brass cap marked, | |
| | <u>1831</u> | |
| | 1917 | |
| | from which, | |
| | A pine, 10 ins. diam., brs. N.88°30'E., 221 lks. dist. | |
| | marked $\frac{1}{4}$ S.7 B.T. | |
| | Enter scattering timber and undergrowth, brs. N.W. & S.E. | |
| 52.35 | Top of ridge, brs. N.W. & S.E.; descend. | |
| 73.60 | Draw, course S.60° E. | |
| 76.60 | Descend steep E. slope, 170 ft. to | |
| 82.37 | True point for Cor. of Tps. 1 & 2, Rs. 34 & 35 E. | |
| | Land; mountainous. | |
| | Soil: shallow light loam, 2nd rate. | |
| | Timber; pine and fir. | |
| | Undergrowth; pine and willow. | |